

ADDENDUM #2: STORM DRAINAGE IMPROVEMENTS

PROJECT AREAS 03, 09, 26

PROJECT NO: 2015-03

May 20, 2015

- Alternate #1 48" Equiv. RCPA pipe CAN NOT be substituted for HP or HDPE pipe due to lack of cover. Please quote this as shown and do not include this under the Substitute pricing section.
- HP or HDPE Pipe with corrugated metal end sections may also be used in place of RCP. A revised proposal sheet is attached for your use.

ADDENDUM #2 PROPOSAL

TO THE CITY OF SEDALIA, MISSOURI:

Pursuant to and in compliance with the Notice to Contractors and having examined the plans and specifications with related documents and the site(s) of the proposed work, the undersigned bidder proposes and agrees, if this proposal is accepted, to furnish all labor, materials, tools, supplies, equipment and supervision and to do all other work necessary for the **STORM DRAINAGE IMPROVEMENTS – PROJECT AREAS 03, 09, 26, Project 2015-03, dated April 23, 2015,** as noted in these contract documents for the following price(s):

BASE BID – PROJECT AREAS 03 and 09

Item No.	Description	Unit	Estimated Quantity	Unit Cost	Amount
STORM DRAINAGE IMPROVEMENTS					
1	Demolition and Site Preparation	LS	1		
2	Traffic Control	LS	1		
3	Construction Staking	LS	1		
4	Unclassified Excavation	CY	14		
5	Embankment	CY	30		
6	Curb and Gutter	LF	89		
7	Concrete Driveway (6")	SY	184		
8	Remove and Replace Asphalt Pavement	SY	30		
9	Sidewalk (4")	SY	33		
10	15" RC End Section	EA	1		
11	18" RC End Section	EA	1		
12	4'x4' Type A Curb Inlet	EA	1		
13	8'x3' Type A Curb Inlet	EA	1		
14	8'x3' Junction Box	EA	1		
15	15" RCP	LF	42		
16	18" RCP	LF	102		
17	24" RCP	LF	75		
18	Seeding	ACRES	0.2		
19	Erosion Control	LS	1		

TOTAL AMOUNT OF BASE BID: \$ _____

**SUBSTITUTE HDPE WITH CORRUGATED METAL END SECTIONS: \$ _____
(ONLY INSERT ADDITION/SUBTRACTION FROM ORIGINAL BASE BID)**

**SUBSTITUTE HP WITH CORRUGATED METAL END SECTIONS: \$ _____
(ONLY INSERT ADDITION/SUBTRACTION FROM ORIGINAL BASE BID)**

ADD ALTERNATE 1 – PROJECT AREA 26

Item No.	Description	Unit	Estimated Quantity	Unit Cost	Amount
	STORM DRAINAGE IMPROVEMENTS				
1	Demolition and Site Preparation	LS	1		
2	Traffic Control	LS	1		
3	Construction Staking	LS	1		
4	Unclassified Excavation	CY	279		
5	Embankment	CY	122		
6	Concrete Driveway (6")	SY	46		
7	Sidewalk (4")	SY	4		
8	18" RC End Section	EA	1		
9	48" Equiv. RC End Section (NO SUBSTITUTE)	EA	1		
10	8'x3' Junction Box	EA	1		
11	18" RCP	LF	34		
12	48" Equiv. RCPA (NO SUBSTITUTE)	LF	64		
13	Riprap (MoDOT Type 3 Rock Ditch Liner)	SY	150		
14	Seeding	ACRES	0.1		
15	Turf Reinforcement Mat (TRM)	SY	250		
16	Erosion Control	LS	1		

TOTAL AMOUNT OF ADD ALTERNATE 1: \$ _____

**SUBSTITUTE HDPE WITH CORRUGATED METAL END SECTIONS: \$ _____
(ONLY INSERT ADDITION/SUBTRACTION FROM ALTERNATE 1)**

**SUBSTITUTE HP WITH CORRUGATED METAL END SECTIONS: \$ _____
(ONLY INSERT ADDITION/SUBTRACTION FROM ALTERNATE 1)**

TOTAL AMOUNT OF BASE BID + ADD ALTERNATE 1:

\$ _____

TOTAL AMOUNT OF SUBSTITUTION HDPE FOR BASE BID + ADD ALTERNATE 1:

\$ _____

TOTAL AMOUNT OF SUBSTITUTION HP FOR BASE BID + ADD ALTERNATE 1:

\$ _____

Bidder acknowledges receipt of the following addenda, which has been considered in the preparation of this bid:

Addendum No. _____

Dated: _____

Addendum No. _____

Dated: _____

Addendum No. _____

Dated: _____

The undersigned agrees, if this proposal is accepted, to complete the work within **a period of 45 calendar days** from the date of the Notice to Proceed.

NAME OF BIDDER:

BY:

TITLE:

ADDRESS:

DATE: _____